FLOOR PLAN

SCALE: 1/8" = 1'-0"

627'-0" (TO FACE OF 8" CONCRETE TILT-UP PANEL)

LEASE SPACE 100 | LEASE SPACE 200 | LEASE SPACE 300 | LEASE SPACE 400 | LEASE SPACE 500 | LEASE SPACE 600 | LEASE SPACE 700 | LEASE SPACE 800 | LEASE SPACE 900 | LEASE SPACE 1000 | LEASE SPACE 100 | LEASE SPACE 200

SEE ENLARGED ENTRANCE PLAN "A", SHEET A2.2

SEE ENLARGED ENTRANCE PLAN "B", SHEET A2.2

SEE ENLARGED ENTRANCE PLAN "C", SHEET A2.2

5'-0" W. X 4'-6" H. KNOCKOUT PANEL FOR FUTURE WINDOW

1 1/2" BALL VALVE (TYP.)

2" INSULATED COPPER OVERHEAD WATER LINE

6" PVC SANITARY SEWER STARTING MIN. DEPTH AT -2'-0" AFF AT EACH END

4,000 PSI 5" CONCRETE SLAB W/ 6X6 X 10.0 X10.0 WIF OVER 8 MIL. POLY VAPOR BARRIER OVER 6" VDOT NO. 57 STONE FILL - PROVIDE SAW CUT JOINTS AT 16'-8" O.C. - CENTERED ON GRID EACH WAY BETWEEN COLUMN LINES

NOTE:
PROVIDE ADD ALTERNATE FOR THE USE OF 2A OR 21B COMPACTED STONE IN PLACE OF 57 STONE UNDER SLAB.

PROPOSED (4) METER 4 CAPACITY METER TROUGH LOCATION

LINE OF CONCRETE INFILL 1'-0" FROM INTERIOR FACE OF CONCRETE PANELS

SEE ENLARGED STAIR PLAN SHEET A2.2

PROPOSED GAS METER LOCATION

2"# TELEPHONE CONDUIT SUSPENDED IN JOISTS ABOVE (ONE PER BAY)

NOTE:
PROVIDE ADD ALTERNATE FOR THIS DOOR TO BE A 12'-0" X 14' DOOR WITH DRIVE UP RAMP

5'#L PIPE BOLLARDS (SEE DETAIL A4.2)

PROPOSED (6) METER 1 CAPACITY METER TROUGH LOCATION

PREFINISHED DOWNSPOUT (DOWNSPOUT LOCATION FOR ILLUSTRATION ONLY, LOCATIONS TO BE APPROVED BY OWNER)

1" FIRE ALARM CONDUIT AROUND ENTIRE PERIMETER - PROVIDE JUNCTION BOXES AT EACH EXTERIOR DOOR WITH PULL STRINGS

NOTE:
PROVIDE ADD ALTERNATE FOR THIS DOOR TO BE A 12'-0" X 14' DOOR WITH DRIVE UP RAMP

ADA AREA OF RESCUE ASSISTANCE (TYP.)

FIRE SPRINKLER RISER ROOM 102

FLOOR DRAIN TO DAYLIGHT AT CURB

PROVIDE (2) SHEETS 3/4" PLYWOOD - CUT TO FIT - FOR TELEPHONE EQUIPMENT

3 5/8" METAL STUD AT 16" O.C. WITH 1/2" GYP. WALLBOARD EACH SIDE W/ 3 1/2" FIBERGLASS BATT SOUND INSULATION (U/ A STC RATING OF 45 MIN. (CARRY ASSEMBLY TO UNDERSIDE OF DECK)

6" # CONDUIT STUBBED 5'-0" FROM FACE OF BUILDING FOR TELEPHONE SERVICE - PLUS (4) ADDITIONAL 6"# CONDUITS STUBBED 5'-0" FROM FACE BUILDING FOR FUTURE USE - VERIFY QUANTITY WITH OWNER

PROPOSED (6) METER 1 CAPACITY METER TROUGH LOCATION

Make sure the sidewalk extends under roof access ladder

FIXED ACCESS LADDER W/ CAGE AND SECURITY DOOR O'KEEFE'S #532 OR EQUAL

NOTE:
FINAL DOWNSPOUT LOCATIONS AND SIZES TO BE FIELD VERIFIED WITH OWNER AND ROOFER.